



September 21, 2021

Contactors,

Please see RFI answers for the Prospector Park Bid.

- Can you clarify the topsoil requirements? The specs say 8" in planters, does that apply to the seed areas? Also can clarify the mix requirements?
 - o **There are no planters in the bid. The reseeded area will receive 4-inch of top soil, we will be sending out an Addendum shortly to add a top soil bid item.**
- The bid item for asphalt says 3", the detail shows 2.5" which one applies?
 - o **The depth of the asphalt is 3" inches thick. The bid item #20 is the correct depth.**
- I cannot see where the perf pipe item goes- is that just the drains for the fountains? (approx. 25')
 - o **The Perforated Drain line is for the Drinking Fountain and and Dog Wash, see sheet 3 of 7, and the detail sheet is on page DT-2**
- Is there a rock type required for the riprap?
 - o **The riprap bid item is item #16 – 6-inch Rip Rap, 12-in thick. The rip rap needs to meet 2017 APWA – Section 31.37.00**
- I assume the controller will be installed in the adjacent restroom by others it be mounted on the exterior or interior? Will we need to tie in the power or will it be stubbed for us?
 - o **The plan is to connect the controller to the restroom once it has been completed (by others). The power will not be available until the restroom is complete, we are hoping to use a temporary battery and stand until it can be attached to the restroom.**

Adam Ginsberg

Staff Engineer

Public Works | Cottonwood Heights

801.944.7063

2277 East Bengal Boulevard

Cottonwood Heights, UT 84121

www.cottonwoodheights.utah.gov